

工程指示 / 要求簡箋(E.I.)

工程指示編號：EI/ 2422/20

修改版次：

工程編號：J851

工程名稱：青衣明翹滙

工程項目：露台欄河辦房層地盤用玻璃

收件人：Maggie Lor

發件人：Joe Chan

日期：11/9/2020

要求提供 / 確認 事項：

- | | | |
|------------------------------------|-------------------------------------|-------------------------------|
| <input type="checkbox"/> 初步鋁料 B.M. | <input type="checkbox"/> 加工拆圖，然後生產 | <input type="checkbox"/> 尺寸表 |
| <input type="checkbox"/> 正式鋁料 B.M. | <input type="checkbox"/> 技術上資料 / 指示 | <input type="checkbox"/> 報價 |
| <input type="checkbox"/> 配件 B.M. | <input type="checkbox"/> 樣辦或貨品說明書 | <input type="checkbox"/> 分判合約 |
| <input type="checkbox"/> 其他：_____ | | |

內容：

請依附件資料，生產玻璃，送地盤

請按 BS EN 14179-1:2016 標準做熱浸測試。

請在 30/9/2020 前完成上列要求。

附有關圖紙 / 文件：

14頁

以上項目為：

- 原合約工程包 原合約工程加 / 減賬 新工程報價

原因：-

分發東莞各部門：

- () 生產技術總監 連附件 () 技術部 連附件 () 生產部 連附件 () 機械設計部 連附件
 () 採購部 連附件 () 生產統籌部 連附件
 () 質檢部 連附件 () 會計部 連附件 () 報關組 連附件 () 其他 _____ 連附件

分發香港各部門：

- () 行政部 連附件 () 會計部 連附件 () 統籌部 連附件 (✓) 工程部地盤科文 連附件 積哥
 () 採購部 連附件 () QS 部 連附件 () 維修部 連附件 () 其他 _____ 連附件


傳遞編號：

發件人簽署：

項目經理簽署：


積哥
 J.C.
 P.P. J.C.

①

 美特鋁質 有限公司 MEDI Aluminium Fabricator Ltd.		工程號: J-851	計算: 大明	日期: 11/9/2020	送呈: 胡哥			
地盤用玻璃B.M.表		地盤名稱: TYTL190	核對: 日期:	日期: 日期:	副本: A/C Code:			
B/M編號:		項目類別: 露台欄河	批准: 日期:	日期: 日期:	A/C Code:			
修改內容		修改版次:	總計玻璃面積 (平方米): 12.442		此B/M依據			
序號	玻璃編號	顏色與類型	厚度 (mm)	玻璃尺寸		數量 (塊)	總面積 (平方米)	備注
1	GL-01	8mm Clear Tempered + 1.52 PVB + 8mm Clear Tempered (LIMINATED GLASS)	17.52	寬度 (mm)	高度 (mm)	2	0.131	
2	GL-02		60.0	1090.0	2	0.131		
3	GL-03		17.52	680.0	1090.0	5	3.706	
4	GL-04		17.52	710.0	1090.0	2	1.548	
5	GL-05		17.52	160.0	1090.0	1	0.174	
6	GL-06		17.52	260.0	1090.0	2	0.567	
7	GL-07		17.52	1944.0	1090.0	2	4.238	
8	GL-08		17.52	1907.0	1090.0	1	2.079	
9	GL-09		17.52	1964.0	1090.0	1	2.141	
10	GL-10		17.52	1777.0	1090.0	1	1.937	
11	GL-11		17.52	2174.0	1090.0	1	2.370	
			17.52	2314.0	1090.0	1	2.522	
			合計		19	12.442		



加工注意事項:

- 1) 本表中所採用之玻璃為信義玻璃廠出品之玻璃原片
- 2) 本表中所有玻璃對角線尺寸偏差要求不超過正負2mm。
- 3) 本表中所有玻璃要求粗磨邊處理並倒棱角。
- 4) 本表中不同種類玻璃參照玻璃加工圖加工。
- 5) 本表中所有強化玻璃均需HEAT SOAK TEST。
- 6) 本表中所有強化玻璃之入爐方向均以寬度方向進入。
- 7) 本表中所有玻璃成品均需注明室內外面及其玻璃編號，以便識別。



美特鋁質有限公司
MIDI Aluminium Fabricator Ltd.


工程號	J851	類別		物料號	-
地盘	青衣190	制圖	W. E. X	圖號	GL01
修改	-	图纸名称	玻璃加工图	數量	-
日期	-	材料	GLASS	單件重量	- (KG)



11	GL-11	2314	1
10	GL-10	2174	1
9	GL-09	1777	1
8	GL-08	1964	1
7	GL-07	1907	1
6	GL-06	1944	2
5	GL-05	260	2
4	GL-04	160	1
3	GL-03	710	2
2	GL-02	680	5
1	GL-01	60	2
序号	玻璃图号	W	数量

NOTES
1. ALL DIMENSION IN mm
2. ALL EDGE CHAMFER 1x1x45°

12A FLAT A (MIR.)




FACADE COLOUR	
BALUSTRADE OF RAILING (1-17F)	DARK GREY
BALUSTRADE OF RAILING (18-33F)	WHITE
AL01	DARK GREY
AL02	WHITE
AL03	SANDY BROWN
AL04	TIMBER PATTERN

BAL. TYPE	TOWER	F.L.R.	FLAT	QTY
B1 (MIR.)	T2	1/F	A	1
		2/F TO 31/F	A	26
B9 (MIR.)	T2	32/F	A	1
		33/F	A	1



3

12A FLAT A




FACADE COLOUR	
BALUSTRADE OF RAILING (1-17F)	DARK GREY
BALUSTRADE OF RAILING (18-33F)	DARK GREY
AL01	DARK GREY
AL02	WHITE
AL03	SANDY BROWN
AL04	TIMBER PATTERN

BAL. TYPE	TOWER	F.L.R.	FLAT	QTY
B21	T2A	1/F	A	1
	T2A	2/F TO 31/F	A	26
B26	T2A	32/F TO 33/F	A	2




12A FLAT B




FACADE COLOUR	
BALUSTRADE OF RAILING (1-17F)	WHITE
BALUSTRADE OF RAILING (18-32F)	DARK GREY
AL01	DARK GREY
AL02	WHITE
AL03	SANDY BROWN
AL04	TIMBER PATTERN

BAL. TYPE	TOWER	F.L.R.	FLAT	QTY
B2 (MIR.)	T2	1/F	B	1
		2/F TO 31/F	B	26
B10 (MIR.)	T2	32/F	B	1




12A FLAT B



FACADE COLOUR	
BALUSTRADE OF RAILING (2-17F)	DARK GREY
BALUSTRADE OF RAILING (18-32F)	DARK GREY
AL01	DARK GREY
AL02	WHITE
AL03	SANDY BROWN
AL04	TIMBER PATTERN

BAL. TYPE	TOWER	F.L.R.	FLAT	QTY
B20	T2A	2/F TO 31/F	B	26
B25	T2A	32/F TO 33/F	B	2



BD. REF. :
F.S.D. REF. :

NOTE :
1. All dimensions are in mm.
2. All elevations are viewed from outside.
3. All dimensions to be verified on site before construction.
GENERAL NOTES

- Legend :
- 1. F.L. --- Finished floor level
 - 2. S.F.L. --- Standard floor level
 - 3. (MIR.) --- Mirrored Detail



NO. DATE REVISION

CLIENT : 佳明集團控股有限公司
GRAND MINE GROUP HOLDINGS LIMITED

MAIN CONTRACTOR : GRAND TECH CONSTRUCTION CO. LTD.

ARCHITECT : WONG TUNG & PARTNERS LIMITED

STRUCTURAL ENGINEER : C M WONG & ASSOCIATES LTD


MECHANICAL ENGINEER : MTDI 美特銘實有限公司

PROJECT : RESIDENTIAL DEVELOPMENT AT TSING YI TOWN LOT 100 SAN SHAN ROAD

TITLE : TITLE-1
TITLE-2
TITLE-3
TITLE-4


JOB NO. : 1-851
DRAWN BY : D99WNS79
DATE :
CHKD BY :
SCALE : AT
DATE :
DWG. NO. :
DWSG. NO. :
REV. : REV.

T2A FLAT C




FACADE COLOUR	
BAUSTRADE OF RAILING (2-17F)	DARK GREY
BAUSTRADE OF RAILING (18-33F)	DARK GREY
CLADDING AT BAL./U/P	A.01 DARK GREY A.02 WHITE A.03 SANDY BROWN A.04 TIMBER PATTERN

BAL TYPE	TOWER	F.LR.	FLAT	QTY
B19	T2A	2/F TO 31/F	C	26
B24	T2A	32/F TO 33/F	C	2




T2A FLAT D




FACADE COLOUR	
BAUSTRADE OF RAILING (2-17F)	DARK GREY
BAUSTRADE OF RAILING (18-33F)	DARK GREY
CLADDING AT BAL./U/P	A.01 DARK GREY A.02 WHITE A.03 SANDY BROWN A.04 TIMBER PATTERN

BAL TYPE	TOWER	F.LR.	FLAT	QTY
B5	T2A	2/F TO 31/F	0	26
B13	T2A	32/F TO 33/F	0	2



4

T2A FLAT E



FACADE COLOUR	
BAUSTRADE OF RAILING (2-17F)	DARK GREY
BAUSTRADE OF RAILING (18-33F)	DARK GREY
CLADDING AT BAL./U/P	A.01 DARK GREY A.02 WHITE A.03 SANDY BROWN A.04 TIMBER PATTERN




BAL TYPE	TOWER	F.LR.	FLAT	QTY
B5 (MIR)	T2A	2/F TO 31/F	E	26
B13 (MIR)	T2A	32/F TO 33/F	E	2

B.D. REF :
F.S.D. REF :
Note :
1. All dimensions are in mm.
2. All elevations are viewed from outside.
3. All dimensions to be verified on site before construction.

GENERAL NOTES

- Legend :
- 1. F.L.— Finished Floor Level
 - 2. S.F.L.— Structural Floor Level
 - 3. @ — Reserved Field



NO.	DATE	REVISION	BY

CLIENT : 佳明集團控股有限公司
GRAND MING GROUP HOLDINGS LIMITED
MAIN CONTRACTOR : GRAND TECH CONSTRUCTION CO. LTD.


ARCHITECT : HONG TUNG & PARTNERS LIMITED
STRUCTURAL ENGINEER : C M WONG & ASSOCIATES LTD

美特經實有限公司
MIDI ASSOCIATA EXAMINATION S.M.
Unit 6-8, Sunny Industrial Centre, 1/F
610 Chin Kwo Ling Road, Kowloon
Tel: 2489271-4 Fax: (852) 27277688

PROJECT : RESIDENTIAL DEVELOPMENT AT TSING YI TOWN LOT 189 SIA SHAN ROAD

TITLE :
JOB NO. : J-851
DRAWN BY :
DATE :
SCALE :
DWG. NO. :
REV. : REV.

EI 2422 參考用 BM 表

 美特鋁質有限公司 MIDI Aluminium Fabricator Ltd.		工程號:	J-851	計算:	JOE CHAN	日期:	11/9/2020	送呈:	胡哥	
地盤用玻璃B.M.表		地盤名稱:	TYTL190	核對:		日期:		副本:		
BM編號:		項目類別:	露台欄河	批准:		日期:		A/C Code:		
修改內容:		修改版次:		總計玻璃面積 (平方米):			12.442	此BM依據		
序號	修改內容	玻璃編號	顏色與類型	厚度 (mm)	玻璃尺寸			數量 (塊)	總面積 (平方米)	備注
					寬度 (mm)	高度 (mm)	高度 (mm)			
1		GL-01	8mm Clear Tempered + 1.52 PVB + 8mm Clear Tempered (LIMINATED GLASS)	17.52	60.0	✓	1090.0	2	0.131	
2		GL-02		17.52	680.0	✓	1090.0	5	3.706	
3		GL-03		17.52	710.0	✓	1090.0	2	1.548	
4		GL-04		17.52	160.0	✓	1090.0	1	0.174	
5		GL-05		17.52	260.0	✓	1090.0	2	0.567	
6		GL-06		17.52	1944.0	✓	1090.0	2	4.238	
7		GL-07		17.52	1907.0	✓	1090.0	1	2.079	
8		GL-08		17.52	1964.0	✓	1090.0	1	2.141	
9		GL-09		17.52	1777.0	✓	1090.0	1	1.937	
10		GL-10		17.52	2174.0	✓	1090.0	1	2.370	
11		GL-11		17.52	2314.0	✓	1090.0	1	2.522	
				合計			19	✓	12.442	

- 加工注意事項:
- 1) 本表中所採用之玻璃為信義玻璃廠出品之玻璃原片
 - 2) 本表中所有玻璃對角線尺寸偏差要求不超過正負2mm。
 - 3) 本表中所有玻璃要求粗磨邊處理並倒棱角。
 - 4) 本表中不同種類玻璃參照玻璃加工圖加工。
 - 5) 本表中所有強化玻璃均需HEAT SOAK TEST。
 - 6) 本表中所有強化玻璃之入爐方向均以寬度方向進入。
 - 7) 本表中所有玻璃成品均需注明室內外面及其玻璃編號，以便識別。