

工程指示 / 要求簡箋(E.I.)

工程指示編號：EI / 3320 / 21

修改版次：-

工程編號：J - 852

工程名稱：亞皆老街中電

工程項目：Glass Cladding 大貨 廠用玻璃 B.M. (T1-T3: 1-23/F) (240 件)

收件人：Maggie/ 生統

發件人：Ant Yeung

日期：26/04/2021

要求提供 / 確認 事項：

- | | | |
|------------------------------------|-------------------------------------|-------------------------------|
| <input type="checkbox"/> 初步鋁料 B.M. | <input type="checkbox"/> 加工拆圖，然後生產 | <input type="checkbox"/> 尺寸表 |
| <input type="checkbox"/> 正式鋁料 B.M. | <input type="checkbox"/> 技術上資料 / 指示 | <input type="checkbox"/> 報價 |
| <input type="checkbox"/> 配件 B.M. | <input type="checkbox"/> 樣辦或貨品說明書 | <input type="checkbox"/> 分判合約 |
| <input type="checkbox"/> 其他：_____ | | |

內容：

則即 40047 和 T. 的 玻璃

請按 B.M. 訂購 T1-T3: 1-23/F 的 Glass Cladding 玻璃送廠用. 共 240 件.

EI2820 已生產及出貨 T1-T3: 3-6/F 的玻璃.

HS: 70T 反光片

請在 2021.05. 15 前完成上列要求。

附：1 頁 BM+ 1 頁 BM 參考+ 1 頁加工圖+ 3 頁 Reference

以上項目為：

- 原合約工程包 原合約工程加 / 減賬 新工程報價

原因：-

分發東莞各部門：

- | | | | |
|--------------------------------------------------------------|-----------------------------------------------------------------------------------|--------------------------------------------------------------|---------------------------------------------------------------------|
| <input type="checkbox"/> 生產技術總監 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 技術部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 生產部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 機械設計部 <input type="checkbox"/> 連附件 |
| <input type="checkbox"/> 採購部 <input type="checkbox"/> 連附件 | <input checked="" type="checkbox"/> 生產統籌部 <input checked="" type="checkbox"/> 連附件 | <input type="checkbox"/> 小羅 & 清 <input type="checkbox"/> 連附件 | |
| <input type="checkbox"/> 質檢部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 會計部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 報關組 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 其他 <u>楊榮輝</u> <input type="checkbox"/> 連附件 |

分發其他分判：

- 水洪 連附件

分發香港各部門：

- | | | | | |
|---------------------------------------------------------------------------------|------------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------------|----|
| <input type="checkbox"/> 行政部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 會計部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 統籌部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 工程部地盤科文 <input type="checkbox"/> 連附件 | 祥哥 |
| <input checked="" type="checkbox"/> 採購部 <input checked="" type="checkbox"/> 連附件 | <input type="checkbox"/> QS 部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 維修部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 其他 _____ <input type="checkbox"/> 連附件 | |

傳遞編號：


HK 882 / 21



發件人簽署：

項目經理簽署：


		工程號:	J852	計算:	CJM	日期:	2021.03.01	送呈:		
		地盤名稱:		核對:		日期:		副本:		
地盤用玻璃B.M.表		項目類別:	GLASS CLDDING (T1~T3, 1F~23F, 不含樣辦層)			日期:		A/C Code:		
BM編號:		修改版次:	A-2021.03.01	總計玻璃面積 (平方米):	215.28					
序號	修改內容	玻璃圖號	顏色與類型	厚度 (mm)	玻璃尺寸		數量 (塊)	總面積 (平方米)	使用位置	加工圖參考
					寬度 (W mm)	高度 (H mm)				
1		G1-41-1	 (G1) 10 mm THK. LOW-IRON HEAT STRENGTHENED GLASS. 	10.0	598.0	1927.0	45	51.86	SG-4001(1~21F) (不含樣板層3, 5, 6F)	GC-G1
2		G1-41-2			598.0	1927.0	45	51.86	SG-4001(1~21F) (不含樣板層3,5,6F)	GC-G1
3		G1-41-3			598.0	2197.0	6	7.88	SG-4001(22~23F)	GC-G1
4		G1-41-4			598.0	2197.0	6	7.88	SG-4001(22~23F)	GC-G1
5		G1-42-1			348.0	1927.0	48	32.19	SG-4002(1~21F) (不含T2T3樣板層3, 5, 6F)	GC-G1
6		G1-42-2			348.0	1927.0	48	32.19	SG-4002(1~21F) (不含T2T3樣板層3, 5, 6F)	GC-G1
7		G1-42-3			348.0	2197.0	6	4.59	SG-4002(22~23F)	GC-G1
8		G1-42-4			348.0	2197.0	6	4.59	SG-4002(22~23F)	GC-G1
9		G1-43-1			813.0	600.0	15	7.32	SG-4003(1~21F) (不含樣板層3, 5, 6F)	GC-G1
10		G1-43-2			813.0	1225.0	15	14.94	SG-4003(1~21F) (不含樣板層3, 5, 6F)	GC-G1
11										
					總合計:		240	215.28		
加工注意事項:		1).本表中之所有玻璃顏色.D20770699。 2).本表中所有玻璃對角線尺寸偏差要求不超過負2mm。 3).本表中玻璃要求粗磨邊處理並倒棱角，而所有玻璃之入爐方向需保持一致。 4).本表中所有玻璃成品均需做雙面保護，用透明靜電膠紙加四周一寸FK白膠紙做雙面加固保護處理。 5).本表中所有玻璃成品均需注明室內外及其玻璃編號，以便識別。								

 美特鋁質 有限公司 MIDI Aluminium Fabricator Ltd.		工程號:	J852	計算:	sde	日期:	2021.02.25	送呈:		
		地盤名稱:		核對:	wsh	日期:	2021.02.26	副本:	<參考用>	
地盤用玻璃B.M.表		項目類別:	GLASS CLDDING (T1~T3, 1F~23F, 不含樣辦層)			日期:		A/C Code:		
BM編號:		修改版次:		總計玻璃面積 (平方米):	215.28					
序號	修改內容	玻璃圖號	顏色與類型	厚度 (mm)	玻璃尺寸		數量 (塊)	總面積 (平方米)	使用位置	加工圖參考
					寬度 (W mm)	高度 (H mm)				
1		G1-41-1	 (G1) 10 mm THK. LOW-IRON HEAT STRENGTHENED GLASS.	10.0	598.0	1927.0	45	51.86	SG-4001(1~21F) (不含樣板層3, 5, 6F)	GC-G1
2		G1-41-2			598.0	1927.0	45	51.86	SG-4001(1~21F) (不含樣板層3,5,6F)	GC-G1
3		G1-41-3			598.0	2197.0	6	7.88	SG-4001(22~23F)	GC-G1
4		G1-41-4			598.0	2197.0	6	7.88	SG-4001(22~23F)	GC-G1
5		G1-42-1			348.0	1927.0	48	32.19	SG-4002(1~21F) (不含T2T3座3.5.6F)	GC-G1
6		G1-42-2			348.0	1927.0	48	32.19	SG-4002(1~21F) (不含T2T3座3.5.6F)	GC-G1
7		G1-42-3			348.0	2197.0	6	4.59	SG-4002(22~23F)	GC-G1
8		G1-42-4			348.0	2197.0	6	4.59	SG-4002(22~23F)	GC-G1
9		G1-43-1			813.0	599.5	15	7.31	SG-4003(1~21F) (不含樣板層3, 5, 6F)	GC-G1
10		G1-43-2			813.0	1225.5	15	14.94	SG-4003(1~21F) (不含樣板層3, 5, 6F)	GC-G1
11										
					总合计:		240	215.28		
加工注意事項:		1).本表中之所有玻璃顏色: D20770699。								
		2).本表中所有玻璃對角線尺寸偏差要求不超過負2mm。								
		3).本表中玻璃要求粗磨邊處理並倒棱角,而所有玻璃之入爐方向需保持一致。								
		4).本表中所有玻璃成品均需做雙面保護,用透明靜電膠紙加四周一寸FK白膠紙做雙面加固保護處理。								
		5).本表中所有玻璃成品均需注明室內外及其玻璃編號,以便識別。								

 藝 杻 跣 斷 崙 登 鼠 伺 MIDI Aluminium Fabricator Ltd.				??		易 蹋?	
				梁?	CJM	2020.09.12	?? GC-G1
党 蜊				? 瞄			? 講 ?BOM桶
??				蠶 拘			奔 离



J-852	? 諮 樣 誰 /GLASS CLADDING	暫	①
		璃	
10mm 厚 LOW-IRON H. S 玻璃			



美特鋁質有限公司
MIDI ALUMINIUM FABRICATOR LTD.

Our ref. MC/40067/852

1st April 2021

Gammon Engineering & Construction Company Limited
139 - 147 Argyle Street,
Kowloon, Hong Kong

By Email & Hand

Attn.: Mr. Dick Yuen / Ms. Penny Chau

Dear Sir,

Re : Design, Supply & Installation of Aluminium Window & Cladding, Curtain Wall, Glass Wall, Louvers and Glass Balustrade Nominated Sub-Contract at K.I.L. 6038RP, K.I.L.6037RP, K.I.L. 6036RP, K.I.L. 6035RP & K.I.L. 6005, Nos. 139-147 Argyle Street, Kowloon.
Resubmission of Glass Sample Board for Bulk Order - Spandrel Glass of Curtain Wall & Glass Cladding (MS072)

Further to the captioned project, we would like to re-submit Spandrel Glass & Glass Cladding Sample Board for your review and comment.

Glass Sample: 10mm Low-iron Heat Strengthened Glass ^{D21010042} D20070686 (10CB)
Back Plate Color: Metallic Bronze UCT201498XL(A)-3
Location: Spandrel Glass of Curtain Wall & Glass Cladding

For details, please refer to the attached photos and glass data.

Thank you for your kind attention.

Yours faithfully,
MIDI ALUMINIUM FABRICATOR LTD.

Marco Tam
Director

Encl

cc. Gammon	- Mr. Chris Kwok / Ms. Myra Li / - Ms. Esther Chung / Ms. Angel Man / - Mr. Jackson Mok / Mr. Sam Tang	(w/e)
Sino	- Mr. Billy Tang / Mr. Jimmy Cheung / - Mr. Terry Wan / Mr. Jaja Wong	(w/e) (Email Only)
AGC	- Mr. Raymond Ho / Mr. Eliot Chan	(w/e) (Email Only)
MFT	- Mr. Brian Leung / Mr. Nigel Lo - Ms. Yoanna Chan / Ms. Cosimo Wong - Mr. Neo Wong	(w/e)

FM/MT/DW/AY/BL/yl

Sample Board for Bulk
Order - Spandrel Glass
of Curtain Wall &
Glass Cladding
(MS072)

Submission Date: 01/04/2021

Approval Date: 23.4.2021

Comment: approved by Approved only

Name:

Signature:

Signature Date:

Approved


Ho

[Signature]

23.4.2021

- IAGC
- ARUP
- WOY

- AXXA
-
-



J3860 - Proposed Residential Development, At 139 - 147 Argyle Street, Kowloon

Submission Ref. no.:	MC/ <u>40067</u> /852	Authorized Representative:	<input type="checkbox"/> Pacific Shine	<input type="checkbox"/> MFT
Material Description:	Resubmission of Glass Sample Board for Bulk Order - Spandrel Glass of Curtain Wall & Glass Cladding (MS072)		<input checked="" type="checkbox"/> AGC	<input type="checkbox"/> AXXA
Submission Date:	01/04/2021	Name:	<input type="checkbox"/> ARUP	<input type="checkbox"/>
Approval Date:	2.4.2021	Signature:	<input type="checkbox"/> WOY	<input type="checkbox"/>
Comment:	Approval on Appearance only.	Signature Date: 24.4.2021		