

工程指示 / 要求簡箋(E.I.)

工程指示編號：EI / 4103 / 21

修改版次：A

工程編號：J - 856

工程名稱：天水圍天榮站

工程項目：佛沙窗 廠用配件 BM

收件人：Maggie / 生統 / 楊榮輝 / 永林 發件人：Eric Liu

日期：14/12/2021

要求提供 /  確認 事項：

- |                                    |                                     |                               |
|------------------------------------|-------------------------------------|-------------------------------|
| <input type="checkbox"/> 初步鋁料 B.M. | <input type="checkbox"/> 加工拆圖，然後生產  | <input type="checkbox"/> 尺寸表  |
| <input type="checkbox"/> 正式鋁料 B.M. | <input type="checkbox"/> 技術上資料 / 指示 | <input type="checkbox"/> 報價   |
| <input type="checkbox"/> 配件 B.M.   | <input type="checkbox"/> 樣辦或貨品說明書   | <input type="checkbox"/> 分判合約 |

內容：

A 版：放行膠顏色(BRONZE)及放行磨耳

請按 BM 訂購配件供廠組裝佛沙窗使用

~~膠顏色未確定，暫停待放行~~

請留意立興配件已在 EI3935 及 EI3891 訂購，此 EI 只需訂分離式拉手

謝謝

請在 2021.12.17 前完成上列要求。

附：

以上項目為：

- 原合約工程包                       原合約工程加 / 減賬                       新工程報價

原因：-

分發東莞各部門：

- |  |   |  |  |
|--|---|--|--|
| <input type="checkbox"/> 生產技術總監 <input type="checkbox"/> 連附件 | <input checked="" type="checkbox"/> 技術部 <input checked="" type="checkbox"/> 連附件   | <input type="checkbox"/> 生產部 <input type="checkbox"/> 連附件    | <input type="checkbox"/> 機械設計部 <input type="checkbox"/> 連附件                    |
| <input type="checkbox"/> 採購部 <input type="checkbox"/> 連附件    | <input checked="" type="checkbox"/> 生產統籌部 <input checked="" type="checkbox"/> 連附件 | <input type="checkbox"/> 小羅 & 清 <input type="checkbox"/> 連附件 |  |
| <input type="checkbox"/> 質檢部 <input type="checkbox"/> 連附件    | <input type="checkbox"/> 會計部 <input type="checkbox"/> 連附件                         | <input type="checkbox"/> 報關組 <input type="checkbox"/> 連附件    | <input checked="" type="checkbox"/> 其他 <input checked="" type="checkbox"/> 連附件 |

分發其他分判：

- (v) 水洪  連附件

分發香港各部門：


- |   |  |   |   |
|---|--|---|---|
| <input type="checkbox"/> 行政部 <input type="checkbox"/> 連附件                       | <input type="checkbox"/> 會計部 <input type="checkbox"/> 連附件  | <input checked="" type="checkbox"/> 統籌部 <input checked="" type="checkbox"/> 連附件 | <input type="checkbox"/> 工程部地盤科文 <input type="checkbox"/> 連附件 |
| <input checked="" type="checkbox"/> 採購部 <input checked="" type="checkbox"/> 連附件 | <input type="checkbox"/> QS 部 <input type="checkbox"/> 連附件 | <input type="checkbox"/> 維修部 <input type="checkbox"/> 連附件                       | <input type="checkbox"/> 其他 <input type="checkbox"/> 連附件      |


傳遞編號：



HK2282 / 21


發件人簽署：

項目經理簽署：

|  |          | 美特鋁質有限公司<br>MIDI Aluminium Fabricator Ltd. | 工程號: J-856         | 計算: 付吉寧           | 日期: 2021.11.20   | 送呈: 胡哥                   |      |       |    |  |
|---|----------|--|--------------------|-------------------|------------------|--------------------------|------|-------|----|--|
|   |          |  | 地盤名稱: 天水圍天榮站       | 核對: 謝永林           | 日期: 2021.11.26   | 副本:                      |      |       |    |  |
| 廠用配件B.M.表   |          | 項目類別: 佛沙窗                                  | 批准:                | 日期:               |                  |                          |      |       |    |  |
| BM編號: 856-WI-M01-F-HP01   |          | A/C Code:                                  |                    |                   |                  | 此BM依據EI/3986A版 第五版施工圖紙計算 |      |       |    |  |
| 序號  | 修改標示     | 配件圖號                                       | 物料編號               | 配件名稱              | 顏色               | 實用                       | 後備   | 總數    | 單位 | 備注                                       |
| 1   |          |  |                    | #8x3/8"圓頭鋼牙       | A4-70            | 17465                    | 535  | 18000 | 粒  | 收反拍線擋膠鋁角 @300c/c                         |
| 2   |          |  |                    | #9x1"圓頭鋼牙         | A4-70            | 78560                    | 1440 | 80000 | 粒  | 收窗框用(16粒/生, 8粒/梗)                        |
| 3   |          |  |                    | #9x1-3/4"平頭鋼牙     | A4-70            | 17465                    | 535  | 18000 | 粒  | 收反拍線 @300c/c                             |
| 4   |          |  |                    | M5x30mm平頭機絲       | A4-70            | 49303                    | 697  | 50000 | 粒  | 收夾通 (@300c/c)                            |
| 5   |          |  |                    | 3/16x1/4"平頭機絲     | A4-70            | 53140                    | 860  | 54000 | 粒  | 收窗玉用(16粒/玉)                              |
| 6   |          |  |                    | 3/16x3/8"平頭機絲     | A4-70            | 53140                    | 860  | 54000 | 粒  | 收窗玉用(16粒/玉)                              |
| 7   |          |  |                    | 3/16"x3/8"平頭機絲    | A4-70            | 13160                    | 340  | 13500 | 粒  | 收扇撐 2粒/隻                                 |
| 8   |          |  |                    | 3/16x1/2"圓頭機絲     | A4-70            | 3290                     | 110  | 3400  | 粒  | 收70窗拈用(1隻/窗)                             |
| 9   |          |  |                    | 3/16x3/8"平頭機絲     | A4-70            | 29610                    | 690  | 30300 | 粒  | 收多點鎖夾巴(3粒/夾巴)                            |
| 10  |          |  |                    | 3/16"x3/8"圓頭機絲    | A4-70            | 26320                    | 680  | 27000 | 粒  | 用於收扣碼(2粒/隻)                              |
| 11  |          |  |                    | 3/16"x3/8"圓頭機絲    | A4-70            | 65800                    | 850  | 66650 | 粒  | 收扇撐 10粒/隻                                |
| 12  | EI3935已訂 |  | 立興MLDFOB-18<br>正常款 | 手柄                | 深銀灰<br>820BC3638 | 3255                     | 40   | 3295  | 隻  | (配18mm長方軸, 螺絲)                           |
| 13  |          |  | 立興MLDFOB-18<br>分離式 | 手柄                | 深銀灰<br>820BC3638 | 35                       | 2    | 37    | 隻  | 圖號: J856-SD-PW-5309窗使用<br>(配18mm長方軸, 螺絲) |
| 14  | EI3935已訂 |  | 立興GTAO-50          | 25MM平收單項傳動器(50孔位) | 鋅合金              | 3290                     | 40   | 3330  | 個  | 用於生窗(配螺絲)                                |
| 15  | EI3935已訂 |  | 立興NBSF             | 窗框扣碼(大)           | 黑色               | 6580                     | 80   | 6660  | 個  | 2組/窗                                     |
| 16  | EI3935已訂 |  | 立興NBSS             | 窗玉扣碼(16MM)        | 黑色               | 6580                     | 80   | 6660  | 個  | 2組/窗                                     |
| 17  | EI3935已訂 |  | 立興KMPI/ABCR        | 多點鎖內鎖型鎖口          | 電光鉻              | 9870                     | 120  | 9990  | 個  | 3組/窗                                     |
| 18  | EI3935已訂 |  | 立興ACRP-13.5        | 多點鎖13.5MM高傳動珠     |                  | 9870                     | 120  | 9990  | 個  | 3組/窗(鎖點高13.5mm)                          |
| 19  | EI3935已訂 |  | 立興N8262(單孔斜面)      | 單面斜孔傍膠            | 黑色               | 3290                     | 40   | 3330  | 個  | SH窗1隻/窗                                  |
| 20  | EI3891已訂 |  |                    | 立興HHMS-N16扇撐      | 不鏽鋼              | 6580                     | 80   | 6660  | 隻  | SH窗用                                     |
| 21  |          |  | J837-CWG-S1        | 膠條                | 黑色               | 27737                    | 563  | 28300 | 米  | 窗玉防水膠條                                   |
| 22  | A放行      |  |                    | D.C.791防水膠        | Bronze           | 1532                     | 28   | 1560  | 支  | 反拍線位用 300ml/支                            |
| 23  | A放行      |  |                    | D.C.791防水膠        | Bronze           | 1303                     | 22   | 1325  | 支  | 夾通外封口用 300ml/支                           |
| 24  | A放行      |  |                    | D.C.791防水膠        | Bronze           | 3290                     | 60   | 3350  | 支  | 筍口, 碰口位絲坑防水 1支/窗 300ml/支                 |

|  | 美特鋁質有限公司                       | 工程號:        | J-856  | 計算:         | 付吉寧   | 日期:   | 2021.11.20 | 送呈:                      | 胡哥 |                        |
|---|--------------------------------|-------------|--------|-------------|-------|-------|------------|--------------------------|----|------------------------|
|   | MIDI Aluminium Fabricator Ltd. | 地盤名稱:       | 天水圍天榮站 | 核對:         | 謝永林   | 日期:   | 2021.11.26 | 副本:                      |    |                        |
| 廠用配件B.M.表   |                                | 項目類別:       | 佛沙窗    | 批准:         |       | 日期:   |            |                          |    |                        |
| BM編號: 856-WI-M01-F-HP01   |                                | A/C Code:   |        |             |       |       |            | 此BM依據EI/3986A版 第五版施工圖紙計算 |    |                        |
| 序號  | 修改標示                           | 配件圖號        | 物料編號   | 配件名稱        | 顏色    | 實用    | 後備         | 總數                       | 單位 | 備注                     |
| 25  |                                |             |        | 泡泡膠紙        | 白色    | 66    | 4          | 70                       | 卷  | 1mX100m一卷(包裝用)         |
| 26  |                                |             |        | 透明膠紙        | 透明    | 792   | 28         | 820                      | 卷  | 45m/卷 (配泡泡膠紙包裝用)       |
| 27  |                                |             |        | 四寸保護膠紙      | 白色    | 951   | 49         | 1000                     | 卷  | 23m/卷                  |
| 28  |                                |             |        | 三寸保護膠紙      | 白色    | 4374  | 106        | 4480                     | 卷  | 23m/卷                  |
| 29  |                                |             |        | 二寸保護膠紙      | 白色    | 5608  | 142        | 5750                     | 卷  | 23m/卷                  |
| 30  |                                |             |        | 一寸保護膠紙      | 白色    | 9428  | 272        | 9700                     | 卷  | 23m/卷                  |
| 31  | A放行                            | J856-MR70-1 |        | 70窗摩耳       | 熱浸鋅   | 74620 | 1380       | 76000                    | 個  | 70窗預製摩耳 (@300c/c)      |
| 32  | A放行                            | J856-MR50-1 |        | 50窗摩耳       | 熱浸鋅   | 1120  | 180        | 1300                     | 個  | 50窗預製摩耳 (@300c/c)      |
| 33  |                                |             |        | M5x12mm圓頭機絲 | A4-70 | 3290  | 210        | 3500                     | 套  | 收水線碼裝置 1粒/窗 (配1螺母,1平介) |
| 34  |                                |             |        | M5x12mm圓頭機絲 | A4-70 | 3290  | 210        | 3500                     | 粒  | 收水線碼裝置 1粒/窗            |

|   |  |   |  |   |
|---|--|---|--|---|
|  <b>YEE FAI CONSTRUCTION COMPANY LTD.</b><br>怡輝建築有限公司  |  | <b>MATERIAL SUBMISSION</b>  |  |   |
| PROJECT :   | Property Development at LRT Tin Wing Stop at Tin Shui Wai on Lot No. TSWTL23 | Document Ref.:  | TSWTL23/MS-0519  |   |
| We submit herewith the following General Submission to <b>LWK &amp; Partners (HK) Ltd.</b><br>Attn: Ms. Carmen Wong / Mr. Bryant Kam / Mr. Jason Ho   |  | Sub-contractor:   | <b>Midi Aluminium Fabricator</b>   |   |
| for <input checked="" type="checkbox"/> approval / <input type="checkbox"/> information / <input type="checkbox"/> Others, please specify : _____   |  | <input type="checkbox"/> Re-submission /<br><input type="checkbox"/> Supplementary  |  |   |
| <b>SUBJECT: Material Submission of Dowsil 791 Colors Sealant</b>  |  |   |  |   |
| DETAILS: The following material to be used in the above project is <input checked="" type="checkbox"/> in accordance with / <input type="checkbox"/> an alternative equivalent to the Specifications and Drawings, and are submitted for your review and approval.  |  |   |  |   |
| <b>Items</b>  |  | <b>Details</b>  |  |   |
| (a) Material Description  | Silicone weatherproofing sealant   |   |  |   |
| (b) Location to be used   | Window and Louvre at Podium and Tower  |   |  |   |
| (c) Drawing Ref.  | -  |   |  |   |
| (d) Brand Name  | Dow  |   |  |   |
| (e) Model   | 1) Dowsil TM 791   |   |  |   |
| (f) Manufacturer  | Dow  |   |  |   |
| (g) Source of Origin  | China  |   |  |   |
| (h) Supplier  | Midi Aluminium Fabricator Ltd.- Bon Pacific Building Materials (HK) Co. Ltd. |   |  |   |
| This submission is attached with the following:   |  |   |  |   |
| <input type="checkbox"/> Sample <input type="checkbox"/> Test report / certificate <input checked="" type="checkbox"/> Sample photo<br><input type="checkbox"/> Catalogue <input type="checkbox"/> Job Reference. <input type="checkbox"/> Compliance List<br><input type="checkbox"/> Data/Specification <input checked="" type="checkbox"/> Installation Drawing <input type="checkbox"/> Other: Method Statement |  |   |  |   |
| <b>Remarks:</b><br><input checked="" type="checkbox"/> Your prompt reply before <u>1 December 2021</u> would be much appreciated. Thank you for your attention.   |  |   |  |   |
| c.c. (By Email)<br>Best Vision Development Ltd<br>Best Vision Development Ltd (RSM)<br>Sun Hung Kai Architects and Engineers (ST)<br>Sun Hung Kai Architects and Engineers (ME)<br>Ove Arup & Partners Hong Kong Ltd<br>Ove Arup & Partners Hong Kong Ltd (RP)<br>Ove Arup & Partners Hong Kong Ltd (RE)<br>Alpha Consulting Ltd.<br>MTR Property<br>Site Office  |  | Mr. Robert Seng / Mr. Jonathan Chan /<br>Mr. C. C. Lai / Ms. Petrina Cheung<br>Mr. Dimon Ip<br>Mr. C. K. Lau / Mr. Kevin Lam<br>Mr. K. L. Chan / Mr. Michael Chan<br>Mr. Michael Ku / Mr. James Wong /<br>Ms. Karen Chan / Mr. <i>Ivan Lam</i> / Mr. <i>Gary Choi</i><br>Mr. Kent Wong / Ms. Jenny Leung /<br>Mr. Dixon Wong / Mr. Tommy Ng /<br>LWK reply:<br>- No adverse comments.<br>- Subject to Alpha's comments.<br>- The proposed material should fully comply with DA and project specification requirement. | w/e <input checked="" type="checkbox"/> w/o <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input checked="" type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input checked="" type="checkbox"/> <input type="checkbox"/><br><input checked="" type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input checked="" type="checkbox"/> | Authorized Representative<br><br><b>Ben Cheng (PM)</b><br>(Name in Block Letter)<br>18 NOV 2021<br>Submission Date |
| Prepared by:  |  |   |  |   |


|   |  |  |  |  |
|---|--|--|--|--|
| REPLY BY  | <input checked="" type="checkbox"/> LWKP / <input type="checkbox"/> ARUP / <input type="checkbox"/> SHKAE / <input type="checkbox"/> ELEVATION / <input type="checkbox"/> ALPHA / <input type="checkbox"/> _____ |  |  |  |
| REPLY   | <input checked="" type="checkbox"/> Approved <input type="checkbox"/> Approved with comments (A) <input type="checkbox"/> Reviewed as Commented (Resubmission Required) (B)                                      |  |  |  |
| c.c. <b>BRONZE</b> colour sealant selected as marked.   |  |  |  |  |
| Best Vision Development Ltd<br>Best Vision Development Ltd (RSM)<br>Sun Hung Kai Architects and Engineers (ST)<br>Sun Hung Kai Architects and Engineers (ME)<br>Ove Arup & Partners Hong Kong Ltd<br>Ove Arup & Partners Hong Kong Ltd (RP)<br>Ove Arup & Partners Hong Kong Ltd (RE)<br>Alpha Consulting Ltd.<br>MTR Property<br>Site Office |  | Mr. Robert Seng / Mr. Jonathan Chan /<br>Mr. C. C. Lai / Ms. Petrina Cheung<br>Mr. Dimon Ip<br>Mr. C. K. Lau / Mr. Kevin Lam<br>Mr. K. L. Chan / Mr. Michael Chan<br>Mr. Michael Ku / Mr. James Wong /<br>Ms. Karen Chan / Mr. <i>Ivan Lam</i> / Mr. <i>Gary Choi</i><br>Mr. Kent Wong / Ms. Jenny Leung /<br>Mr. Dixon Wong / Mr. Tommy Ng /<br>Mr. W. K. Liu / Ms. Dora Lee<br>Mr. Dominic Yu / Mr. Z. H. Lau<br>Ms. Dorothy Chan / Mr. William Po / Mr. Gary Chan /<br>Mr. Sam Lee / Mr. Tony Chan / Mr. Tommy Chan | w/e <input type="checkbox"/> w/o <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/><br><input type="checkbox"/> <input type="checkbox"/> | Authorized Representative<br><br><b>Bryant Kam</b><br>(Name in Block Letter)<br>13 Dec 2021<br>Reply Date |

Also make hard copy to the following for their retention and information.

1.  PD  PM  SA  ASA  SE  PC  ME  QS  Safety Officer  Site Admin  Others: \_\_\_\_\_

SYC/MA

(\* please cross the box and delete any as appropriate)



## DOWSIL™ 791 Silicone Weatherproofing Sealant

When You Need a Weatherseal Glazing Sealant



- ✓ Excellent weather-proofing performance
- ✓ Meets ASTM Specification C 920
- ✓ High movement capability ±50%

### STANDARD COLORS



黑色  
Black

1個月貨期



灰色  
Grey

1個月貨期



金屬灰  
Metal Grey

3個月貨期



古銅色  
Bronze

1個月貨期



岩灰色  
Limestone

3個月貨期



瓷白色  
Precast White

3個月貨期



白色  
White

1個月貨期



深灰色  
Dark Grey

1個月貨期

Bon Pacific Building Materials (HK) Co. Ltd.  
Tel: (852) 3107-8130 Fax: (852) 3107-8139  
Email: info@bonpacific.com.hk Website: www.bonpacific.com.hk



Color bead on chart is reference only.  
Please refer to product literature for application  
and technical information.