



工程指示 / 要求簡箋 ENGINEER INSTRUCTIONS(E.I.)

工程指示編號:	EI- 4041	修改版本:	D
	HK- 0137 / 22		
工程編號:	J 857	工程名稱:	NKIL6552
收件人:	生統/林哥	發件人:	Nero HO
工程項目:	後裝窗、FD門及趟門 - 地盤用配件BM	日期:	09/06/2022

<input type="checkbox"/> 原合約工程包	<input type="checkbox"/> 原合約工程加 / 減脹 QT-	<input type="checkbox"/> 新工程報價 QT-
---------------------------------	--	------------------------------------

信件批核號碼/圖紙參考編號:	批核模具圖紙編號:
客戶指示附件:	管理內部批簽署:

<input type="checkbox"/> 初步鋁料 B.M.	<input type="checkbox"/> 加工拆圖, 然後生產	<input type="checkbox"/> 尺寸表
<input type="checkbox"/> 正式鋁料 B.M.	<input type="checkbox"/> 技術上資料/指示	<input type="checkbox"/> 報價
<input checked="" type="checkbox"/> 配件 B.M.	<input type="checkbox"/> 樣辦或貨品說明書	<input type="checkbox"/> 分判合約
<input type="checkbox"/> 其他:		

內容:  
按附件修改BM訂購配件送地盤。

D版次是訂窗邊泥, 附頁批核的信件


完成上列要求日期: 17/06/2022

國內

<input type="checkbox"/> 生產技術總監	<input type="checkbox"/> 連附件	<input type="checkbox"/> 技術部	<input type="checkbox"/> 連附件	<input type="checkbox"/> 生產部	<input type="checkbox"/> 連附件
<input type="checkbox"/> 採購部	<input type="checkbox"/> 連附件	<input checked="" type="checkbox"/> 生產統籌部	<input checked="" type="checkbox"/> 連附件	<input type="checkbox"/> 報關組	<input type="checkbox"/> 連附件
<input type="checkbox"/> 質檢部	<input type="checkbox"/> 連附件	<input type="checkbox"/> 會計部	<input type="checkbox"/> 連附件	<input type="checkbox"/> 機械設計部	<input type="checkbox"/> 連附件
<input checked="" type="checkbox"/> 香港辦	<input checked="" type="checkbox"/> 連附件	<input type="checkbox"/> 其他:			

<input type="checkbox"/> 行政部	<input type="checkbox"/> 連附件	<input type="checkbox"/> 會計部	<input type="checkbox"/> 連附件	<input checked="" type="checkbox"/> 統籌部	<input checked="" type="checkbox"/> 連附件	<input type="checkbox"/> 工程部	<input type="checkbox"/> 連附件
<input type="checkbox"/> 採購部	<input type="checkbox"/> 連附件	<input type="checkbox"/> QS部	<input type="checkbox"/> 連附件	<input checked="" type="checkbox"/> 地盤管理	<input checked="" type="checkbox"/> 連附件	<input type="checkbox"/> 維修部	<input type="checkbox"/> 連附件

*發件人簽署:	*組別成員批核簽署:
傳遞編號: HK 137 / 22	項目經理簽署:




美特鋁質有限公司  
MID Aluminum Fabricator Ltd.

工程號: J-857 計算: 吳祎瑜 日期: 4/11/2021 送呈: 細佬  
地盤名稱: 启德6552 核對: 王禮秋 日期: 4/11/2021 副本:  
項目類別: 後裝窗, FD門及趟門 批准: 日期:

BM編號: EI4041D(2022.6.09) A/C Code: 此BM依據20210914收施工圖大樣計算

序號	修改標示	配件圖號	物料編號	配件名稱	顏色	實用	後備	總數	單位	備註
1	B(數量增加)	款式見附图	J857-MR1	摩爾	熱浸鋅	9194	386	9580	粒	用於FD門框頂橫、趟門硬窗、百葉框邊企
2		款式見附图	J857-MR2	摩爾	熱浸鋅	551	377	928	粒	用於百葉框底橫
3		款式見附图	J857-MR3	摩爾	熱浸鋅	551	377	928	粒	用於百葉框頂橫
4		款式見附图	J857-MR4	摩爾	熱浸鋅	710	40	750	粒	用於FD門框底橫
5		款式見附图	J857-MR5	摩爾	熱浸鋅	1900	100	2000	粒	用於F.D門框寬邊企
6		款式見附图	J857-MR6	摩爾	熱浸鋅	1900	100	2000	粒	用於F.D門框窄邊企
7		詳見加工圖號H333		摩耳		5472	178	5650	件	地盤修趟門框
8	B(數量減少)		D.C.791防水膠		黑色	649	61	710	支	300ml/支(牆邊防水膠, 2.8m/支)後裝窗使用
9	B(數量減少)		D.C.791防水膠		黑色	930	90	1020	支	300ml/支, 用於玻璃密封膠(後裝窗使用)
9a	B版新增		D.C.791防水膠		黑色	350	20	370	支	300ml/支(用於FD門牆邊防水膠, 2.8m/支)
9b	B版新增		D.C.791防水膠		黑色	620	30	650	支	300ml/支, 用於FD門玻璃密封膠
9c	B版新增		D.C.791防水膠		黑色	1000	50	1050	支	300ml/支(用於大趟門牆邊防水膠, 2.8m/支)
9d	B版新增		D.C.791防水膠		黑色	3500	100	3600	支	300ml/支, 用於大趟門玻璃密封膠
9e	B版新增		D.C.791防水膠		黑色	800	30	830	支	300ml/支(用於小趟門牆邊防水膠, 2.8m/支)
9f	B版新增		D.C.791防水膠		黑色	2000	100	2100	支	300ml/支, 用於小趟門玻璃密封膠
10			皺紋膠紙			710	35	745	卷	20m/卷
11		材質: EPDM	50(L)x4.5(寬)x9.5(高)側面墊膠		黑色	9728	222	9950	粒	玻璃四周側1/4處 硬度65±5°(每片玻璃16粒)
12		材質: EPDM	50(L)4.5(寬)x8(高)側面墊膠		黑色	4864	111	4975	粒	玻璃四周側1/4處 硬度65±5°(每片玻璃16粒)
13		材質: EPDM	50(L)4(寬)x6(高)側面墊膠		黑色	1888	92	1980	粒	玻璃四周側1/4處 硬度65±5°(每片玻璃8粒)
14	B(數量增加)	材質: EPDM	50(L)3(寬)x10(高)側面墊膠		黑色	5328	200	5528	塊	玻璃室內外側1/4處 硬度65±5°
15	B(數量增加)	材質: EPDM	20x9mm厚墊塊(L=150mm)		黑色	666	64	730	塊	玻璃底1/4處 硬度80°~90°

 <b>美特鋁質有限公司</b> MIDI Aluminium Fabricator Ltd.	工程號:	J-857	計算:	吳祜瑜	日期:	4/11/2021	送呈:	細佬
	地盤名稱:	启德6552	核對:	王禮秋	日期:	4/11/2021	副本:	
	項目類別:	後裝窗, FD門及趟門	批准:		日期:			
<b>地盤用配件B.M.表</b> A/C Code: 此BM依據20210914收施工圖大樣計算								

序號	修改標示	配件圖號	物料編號	配件名稱	顏色	實用	後備	總數	單位	備注
16		材質: EPDM		20x5厚墊塊 (L=150mm)	黑色	1216	24	1240	塊	用於開啟扇趟門玻璃底
17		材質: EPDM		30x5厚墊塊 (L=150mm)	黑色	2432	48	2480	塊	用於固定扇趟門玻璃底
18		材質: EPDM		30x8厚墊塊 (L=150mm)	黑色	472	18	490	塊	用於FD門玻璃底
19				3/16x2"圓頭機絲	S.S-316	138	12	150	粒	修梗夾企
20				3/16x7/8"平頭機絲	S.S-316	138	12	150	粒	修生夾企
21				8x4.5mm方海綿棒	白色	32650	650	33300	米	玻璃打膠用
22	C版(修改)	轉為廠用		# 9x16圓頭鋼牙	S.S#316 A4-70	5530	170	5700	粒	用於地盤修趟門底框
23	B(數量增加)			木尖		5620		5620	個	
24			05-900001-0000-YL	HILTI X-U 27 P8 子彈釘	不銹鋼	20329	1020	21349	粒	固定摩爾
25			05-900000-CD27-00	HILTI 子彈	紅藥	20329	1020	21349	支	固定摩爾
26	D版修改		BondCrete	防水劑(接觸劑)		32	6	38	公升	先訂2分1數量
27	D版增加		HB40	防水粉		3000	250	3250	公斤	先訂3分2數量
28	D版修改		Masterseal 540-Barralastic	防水油		500	100	600	公斤	先訂2分1數量
29	C版(新增)	HILTI HST3-R		M8X75 ANCHOR BOLT		3000	100	3100		大聽提升趟門中立柱頂底鐵碼用
30	C版(新增)	HILTI HST3-R		M8X75 ANCHOR BOLT		1400	50	1450		UP趟門頂底鐵角用
31	C版(新增)	HILTI HST3-R		M12X115 ANCHOR BOLT		1470	100	1570		UP趟門側邊鐵角用
32	C版(新增)			M5.5x25長六角頭自鑽	S.S#316 A4-70	5530	170	5700	粒	用於地盤修趟門底框固定用鋁角
33	C版(新增)	HILTI HST3-R		M10x90膨脹螺栓	A4-70	358	32	390	粒	用於地盤修百叶頂, 底, 側面鐵巴鐵角



**MATERIAL SUBMISSION FORM**

Project Proposed Residential Development at N.K.I.L. No. 6552, Kai Tak Area 4C, Site 2, Kai Tak, Kowloon  
 Works Main Contract  
 Contract No. 19098KL  
 Ref. No. 19098KL / MS / AR - 076 / SL (Rev. 0)  
 Date 31-Mar-2022

To / Attn Ronald Lu & Partners (Hong Kong) Ltd. /  
 Mr. Kelvin Ip/ Mr. Frederick Chan/  
 Ms. Magenta Kietkhajornsiri

Subject **Waterproofing Admixture Coating for Site In-situ Window and Alum. Louver**

Anticipated date of response **14-Apr-2022**

We certify that the submission has been checked and is in full compliance with the Specification & Contract Documents, unless otherwise stated in the remarks.

Adam Wong  
 For and on behalf of  
**E Man Construction Company Limited**

Form RLP/MSF

Received by SE / BS

Received by RLP

cc w/e

MARBLE   Mr. Gilman Wan/  
 EDGE   Mr. Steven Yeung /  
 Ms. Tammy Yuen/  
 Mr. Patrick K.S. Lee/  
 Mr. Marco S.C. Lee/  
 Mr. Albert Yiu

CMW   Mr. Stanley Chan  
 MME   Mr. Rick Tong  
 WTP   Mr. Andy Lee  
 MVA   Mr. Alan Pun  
 RAM   Mr. Calvin K.F. Chiu  
 ADI   Ms. Alison Lee  
 BEC   Mr. Tommy Szeto  
 BTR   Mr. Norman Chan  
 INH   Ms. Agnes Hung  
 COW    
 RE    
 OTHER

**Material Description** Waterproofing Admixture Coating for Site In-situ Window and Alum. Louver

Location Tower Window / Aluminium Louver

Brand Name 1) BondCrete (waterproof coating)  
 2) HB40 (Waterproof Admixture for Grouting)  
 3) Masterseal 540 -Barralstic (waterproof coating)

Country of Origin

Supplier Name

Others (Color)

**Material / Work Reference \***

Specification Reference

Related Dwg. / A.I. Ref. \*

Related BQ Reference

**Submission Attachment**

Sample

Catalogue Data  Attached

Test Report / Certificate \*

Equipment Schedule

Method Statement  Attached

Installation Details  Attached

Job Reference  Attached

Remarks (To list deviations, if any)  
 \* Delete as appropriate

**Review Status / Comment**

Inhibit comments below:  
**Status B**

Further to the review of the captioned submission, please find our comments as follows:  
 - Ensure to comply with Inhibit Technical Spec.  
 - Ensure to comply to manufacturer recommendations in use and installation.

**RESPONSE TO MATERIAL SUBMISSION**

Date

Comments

Replied by SE / Date

Replied by BS / Date

Replied by MQ (INH) late 2022.06.01

cc w/e

MARBLE   Mr. Gilman Wan/  
 EDGE   Mr. Steven Yeung /  
 Ms. Tammy Yuen/  
 Mr. Patrick K.S. Lee/  
 Mr. Marco S.C. Lee/  
 Mr. Albert Yiu

CMW   Mr. Stanley Chan  
 MME   Mr. Rick Tong  
 WTP   Mr. Andy Lee  
 MVA   Mr. Alan Pun  
 RAM   Mr. Calvin K.F. Chiu  
 ADI   Ms. Alison Lee  
 BEC   Mr. Tommy Szeto  
 BTR   Mr. Norman Chan



For and on behalf of  
**Ronald Lu & Partners (Hong Kong) Ltd.**

No review is made of detail dimensions/quantities.  
 The submission is reviewed for general compliance with the design intent only.  
 Any comments or amendments required shall not be deemed to be variation.  
 The review does not release the Contractor from his responsibilities to comply with contract requirements.  
 For resubmission, the Contractor has to highlight or cloud those revision areas in the shop drawing for review.

Legend: A (No objection) C (Amendment & resubmission required)  
 B (No objection, subject to comments as noted) D (Rejected & resubmission required)

w/e